

## **Addendum #1**

**February 12, 2015**

*The following information supplements and/or supersedes the bid documents. This Addendum forms part of the contract documents and is to be read, interpreted, and co-ordinated with all other parts. The cost of all contained herein is to be included in the contract sum. The following revisions supersede the information contained in the original drawings issued for the above-named project to the extent referenced and shall become a part thereof. Acknowledge receipt of this Addendum by inserting its number and date on the Tender Form. Failure to do so may subject the Bidder to disqualification.*

.1 **Mechanical:**

1. **Stockroom Heating:**

1. Provide a separate price for a new 150,000 BTU suspended gas fired unit heater in the Stockroom, located over the receiving door, complete with a wall mounted thermostat.
2. Provide all power wiring and control wiring for a complete installation.
3. Include in price, for the removal of an existing electrical suspended space heater.
4. The Owner will determine at some future time to either retain the existing electrical heater or replace it with a new gas fired heater, depending partially upon this price provided.

2. **Plumbing:**

1. Raise the existing storm water cleanout at the base of the existing column within Units 2 and 3, approximately 24" such that the cleanout will be above the finished floor.
2. The existing sanitary waste line in Units 2 and 3 is to be capped off at the existing lower floor level and not extended to the upper floor level at this time.

.2 **Electrical:**

3. **General:**

1. See electrical wiring requirements under Mechanical above.
2. As part of the demolition work and whenever encountered on or in walls or ceilings to be removed, remove also all existing combination emergency lights and exit lights, all exit lights, emergency lights, horns, thermostats, power outlets, wiring and conduit.

**End of Addendum #1**