

Addendum #7

July 15, 2015

The following information supplements and/or supersedes the bid documents. This Addendum forms part of the contract documents and is to be read, interpreted, and co-ordinated with all other parts. The cost of all contained herein is to be included in the contract sum. The following revisions supersede the information contained in the original drawings issued for the above-named project to the extent referenced and shall become a part thereof. Acknowledge receipt of this Addendum by inserting its number and date on the Tender Form. Failure to do so may subject the Bidder to disqualification.

.1 **General:**

1. **Clarification on Stone:**

1. The stone exterior face material is to be a natural quarried ledge rock stone, with rough rectilinear lines and face, cut in thin sections, to be adhered to the wall, as detailed. Cultured stone will not be acceptable. Stone to be applied horizontally: maximum height of any one stone 2 1/2", minimum 1", in varying lengths 4" to 16" long. Colours to be selected by Owner from a standard range of stone colours expected to be a rich dark blend of colours from charcoal grey to red-brown. Mortared joints to be coloured (not white), narrow (approximately 3/8" max.) and set back from the face of the stone to be almost invisible from a distance of 10 m or more.
2. Contractors to provide a minimum of three alternatives of stone colour blends and three alternative stone layouts (size of stone, pattern of stone and cut/shape of stone) for selection by Architect and Owner.
3. Based on the colour blend selected and the stone layout, the Contractor will prepare a mock-up on site for approval of the stone wall by the Architect and Owner, before proceeding.
4. Because of the importance of this facet of the work, Contractors are requested to carry a price for the installed stone of \$15/SF, based on the wall face of the stone, indicated on the drawings.

.2 **Building Electrical:**

1. **Clarification:**

1. See the attached Addendum E2.

End of Addendum #7

Addendum No. E-2
For Electrical Work For
Mixed Used Development

721 Monaghan Road
Peterborough, Ontario

ISSUED: July 15, 2015

#4-4576

“Contractors to review all changes listed in this document and include in tender price. No extras will be allowed for this work.”

Refer to Electrical E-5, Rev-2, Dated July 15, 2015

1. DP-1 Panel revised.

J.D. Hubbert and Associates

200 Evans Ave., Unit-11, Etobicoke, Ontario M8Z 1J7
e-mail – benny.idh@on.aibn.com

Tel. 416-251-3440x227
Fax. 416-251-9168

721 MONTAGHAN ROAD.

PART - DWG. E-5, REV. 2, DATED July 15, 2015

PANEL IDENT:	DP-1	SERVICE MAINS MOUNTING:	BRK:	208V/120V, 3φ, 4W		NOTES:
				400 AMPS SURFACE		
LOAD DESCRIPTION			BRK	CIRCUITS	BRK	LOAD DESCRIPTION
UNIT 101 SUITE PANEL			100A	1	100A	UNIT 201 SUITE PANEL
			2P	3	2P	
			100A	4	100A	
UNIT 102 SUITE PANEL			2P	5	2P	UNIT 202 SUITE PANEL
			100A	6	100A	
			2P	7	2P	
UNIT 103 SUITE PANEL			100A	8	100A	UNIT 203 SUITE PANEL
			2P	9	2P	
			100A	10	100A	
			2P	11	2P	
			100A	12	100A	
			2P	13	2P	
SPACE			100A	14	100A	UNIT 204 SUITE PANEL
			2P	15	2P	
UNIT 207 SUITE PANEL			100A	16	100A	UNIT 205 SUITE PANEL
			2P	17	2P	
			100A	18	100A	
			2P	19	2P	
UNIT 208 SUITE PANEL			100A	20	100A	UNIT 206 SUITE PANEL
			2P	21	2P	
			100A	22	100A	
			2P	23	2P	
			100A	24	100A	UNIT 208 SUITE PANEL
			2P	25	2P	



NOTE: PROVISIONS FOR INDIVIDUAL SMART METERING IN SUITES

